



श्रीसिद्धिविनायक गणपती मंदिर न्यास, प्रभादेवी, मुंबई - ४०००२८

S. K. Bole Marg, Prabhadevi, Mumbai-400028

(Controlled by Govt. of Maharashtra)

Tel : 022 - 2422 4438

Fax : 022 - 2422 1558

www.siddhivinayak.org

admin@siddhivinayak.org

दिनांक - २९/०९/२०२२

दरपत्रके मागविण्यासंदर्भातील सूचना


विषय :- डकटींगसह चिमणी बसविण्याच्या कामाचे कंत्राट मटेरीयल व मजुरीसह देण्याबाबत...

वरील कामाकरीता अटी, शर्तीबाबतची माहिती व दरपत्रके डाऊनलोड करण्यासाठी न्यासाच्या www.siddhivinayak.org या संकेतस्थळावर भेट द्यावी.


दरपत्रके प्रसिध्दीचा दिनांक	:	बुधवार, दि. २९.१२. २०२२
दरपत्रके सादर करण्याचा अंतिम दिनांक	:	गुरुवार, दि. २९.१२. २०२२
दरपत्रके उघडण्याचा दिनांक	:	गुरुवार, दि. २९.१२. २०२२

अटी व शर्ती :

- १) मूळ दरपत्रकात नमूद अल्युमिनियम डकटींगसह चिमणी बसविण्याच्या कामाकरीता (मटेरीयल व मजुरीसह) मोहरबंद दरपत्रके मागविण्यात येत आहेत. (सर्व कामे माल व मजुरीसह आहेत)
- २) दरपत्रक सादर करण्यापूर्वी प्रत्यक्ष पाहणी करून कामासंबंधीची सविस्तर माहिती घेण्यात यावी.
- ३) मूळ दरपत्रकात नमूद केलेले काम मटेरीयल व मजुरीच्या तपशीलानुसार तसेच न्यासाने निर्गमित केलेल्या कार्यादेशातील नमूद कालावधीत करावयाची आहेत.
- ४) दरपत्रक सादर करताना दरपत्रकात कर वगळून (Excluding GST) दर नमूद करावे. तसेच दरपत्रकात इतर खर्च समावेशक दराचा उल्लेख करावा.
- ५) सदर कामे पूर्ण केल्याची खात्री करून झाल्यानंतर आपले देयक आर. टी. जी. एस. द्वारे अदा करण्यात येईल. सरकारी नियमाप्रमाणे आवश्यक तेथे आयकर कपात केली जाईल.
- ६) उपरोक्त अटी व शर्तीत काही बदल, सुधारणा करण्याचा वा जादा अटी शर्ती विहित करण्याचा अधिकार न्यास व्यवस्थापनाने राखून ठेवला आहे. आपली कोणतीही अट/अटी न्यासावर बंधनकारक राहणार नाहीत.
- ७) दरपत्रकदाराने मोहरबंद दरपत्रकासोबत साक्षांकीत करून सादर करावयाची कागदपत्रे.
 - अ) कंपनी नोंदणी दाखला
 - क) आयकर नोंदणी पॅन कार्ड
 - ड) सेवाकर जी. एस. टी. नोंदणी दाखला
- ८) दरपत्रके भरताना (कर वगळून) रक्कम भरावी.
- ९) कोणतेही कारण न देता दरपत्रक स्विकारण्याचा अथवा नाकारण्याचा अधिकार न्यासास असेल.
- १०) कागदपत्रे सादर करण्यास असमर्थ ठरलेल्या दरपत्रकदाराचे दरपत्रक निवडप्रक्रियेतून बाद करण्यात येईल.


(नंदा मा. राऊत)
कार्यकारी अधिकारी





श्रीसिद्धिविनायक गणपती मंदिर न्यास, प्रभादेवी, मुंबई - ४०००२८

S. K. Bole Marg, Prabhadevi, Mumbai-400028

Tel : 022 - 2422 4438 Fax : 022 - 2422 1558

(Controlled by Govt. of Maharashtra)
www.siddhivinayak.org admin@siddhivinayak.org

मूळ दरपत्रक

दरपत्रकामध्ये खालील बाबी अंतर्भूत करण्यात याव्यात.

दरपत्रकधारकाचे नाव: _____

दरपत्रकधारकाचा कायमचा पत्ता: _____

जी एस टी क्रमांक _____

SR. NO	DESCRIPTION	Unit	Qty.	Supply Rate	Supply Amount	Installation Rate	Installation Amount
1	Providing erecting legged metal scaffolding (cup lock type) 1200 to 1500mm largely free standing using H frames of tubular pipes of minimum 40mm diameter with base plates fixed or adjustable with necessary clamps, couplers, brackets for projections, joint pins, pulleys and other accessories including steel angle or tubular pipe bracings at adequate intervals access platforms of metal or timber planks of span not exceeding 1.5 meter centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes. M.S. tube chalis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work including provision of rubber inserts to pipe ends at point of contact with structure to avoid damage, including access ladders with intermediate platforms the scaffolding to be suitably braced and anchored to the building using support systems created temporarily at opening in walls using vertical and horizontal adjustable props on the exterior side of the structure at any height above ground level. The rate includes covering of all window openings with 6mm thick plywood provision of high density plastic sheets covering to protect architectural details on the entire building face a nylon net to prevent all debris falling onto the pavement required and the safety platform at ground level covering the devotes at ground level etc. complete. (The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once only for execution of all items for such work.)	1	LS				

निमित्त

निमित्त

2	Providing and Fixing Ducting in aluminium 16 gauge for chimney works inclusive of joints - gasket bolting, painting etc. All. Size:33* 33*	80	RFT				
3	Providing cutting fabricating, welding & placing in position stainless steel plates, brackets, Flats, pipes, brackets etc. as given in consultants drawing.	250	KG				
4	Providing and Fixing high density neopad for shock absorption of vibrations and silicon gap filling in chimney ducting wherever necessary with all finished etc.	1	LOT				
5	Providing and fixing 16mm s-s-304.bolt 400mm long anchored with hilt chemical as per the specification mentioned in detailed drawing provided by consultant	40	NOS				
6	Providing and fixing 12mm s-s-304.bolt 150-200mm long as per the specification mentioned in detailed drawing provided by consultant	20	NOS				
7	Removing & refixing marble of any thickness with changes required as per site condiiyons as directed consultant ect.complent.	15	NOS				
8	Providing and fixing pink makrana marble in 22-25 mm thick for external. cladding as per approved design & sizes,joinery given by the architect /Engineer in-charge etc,including providing SS 316 clamp /brass pin connections to the brick/RCC surface,as per approved drawing joinery groove cutting hole drilling backing mother in cement mortar filling joints,polishing etc,complete Approval of Finished Sampil to taken from architect/consultant prior execution work, as directed by engineerin-charge,contractor to also note &consider architect/consultant prior execution work as directed by engineerin-charge,Conteractor to also note &consider in the rate the following 1;extraction of 75mm diameter core upto depth of 150mm inside the brick wall on external surface for making surface to place precast concrete bed block for fixity of marble cladding including finsh the expiosed brick surface with cement mother, applition of bond coat etc. complete 2 Providing and laying in situ M-30.cement of trap/granite/quartzite/gneiss mental for precast bed block of 75mm dia having length of 150mm inside brick masonry including.formwork curing The rate shall also include cost dia fixing precast bed block in the core extracted in exposed brick surface with cement mother.application of bond	QRO	Sqm				
9	Provunding cutting fagricating welding & placing in position structural steel brackets,beams channels etc.,with necessary drilling holes in concrete as directed by Consultants ets,complets	600	KG				
10	Aluminium,folll coated insulation 13mm Nitrile,external on duct along with canvas connection for unit mouch cconnection -fire retardant Collar Damper for exhaust air grill VCD Damper for exhaust air grill etc.	120	RFT				

दरपत्रकारकाची सही व शिक्का

[Handwritten signature]

[Handwritten signature]

